# RATE ANALYSIS – "Flooring in Superstructure”

**1. 2.5 CM Thick cement 1:2:4 floor with neat cement flooring at top. Take 100 Sq.M**

Given:-

| Take 100 Sq.M | | |
|---|---|---|
| Thickness of Cement floor = | 2.5 | CM |
| Cement = | 1 | |
| Sand = | 2 | |
| Aggregate | 4 | |
| For 1 Cum, Cement required is = | 1440 | Kg |
| 1 bag of Cement contained is = | 50 | Kg |
| Given that Sq.M = | 100 | Sq.M |

| Determination of Volume of mortar | | |
|---|---|---|
| Volume of Mortar = | 2.5 | Cu.M |
| Add 10% for unevenes cement base = | 2.75 | Cu.M |
| Add 50% of extra for Dry volume = | 4.125 | Cu.M |
| Quantity of Cement = | 0.59 | Cu.M |
| No of Cement bags required = | 16.97 | Nos |
| No of Cement bags required = | 17 | Nos |
| Quantity of Sand = | 1.18 | Cu.M |
| Quantity of Aggregate = | 2.36 | Cu.M |

| Sl no | Particular of Items | Quantity or No's | Rate/Cum | Amount |
|---|---|---|---|---|
| 1 | Materials | | | |
| | Cement | 17 | 330 | 5610 |
| | Sand | 1.18 | 1300 | 1532.1 |
| | Aggregate | 2.4 | 700 | 1650 |
| | | | | |
| 2 | Labours | | | |
| | Head Mason | 1 | 466 | 466 |
| | Mason | 4 | 456 | 1824 |
| | Mazdoor | 8 | 446 | 3568 |
| | Contengnecies | - | 200 | 200 |
| | | | Total = | 14850.1429 |
| | | | Add 1% of Water Charges = | 148.501429 |
| | | | Total = | 14998.6443 |
| | | | Add 10% of Profit or Loss = | 1499.86443 |
| | | | Grand Total | 16498.5087 |