

RATE ANALYSIS – "Cement Concrete in Foundation"

1. Cement Concrete in foundation with 40 mm gauge brick ballast unit 1 Cum. =
1:5:10 Propotion

Given data :

1 Cum of cement bags contains	1440	Kg
Cement =	1	Cum
Sand =	5	Cum
Aggregate =	10	Cum
Total =	16	Cum

Take 10 Cum.		
Dry weight:=	Wet weight + 54% of wet-weight	Cum.
Wet weight =	10	Cum
Dry weight =	15.4	Cum
		Cum
Qunatity of cement =	1.0	Cum
Qunatity of Sand =	4.8	Cum
Quantity of Aggregate =	9.6	Cum
Number of cement bags in Cum =	0.0347	Cum
Total number of cement bags =	27.72	Bags
Total number of cement bags =	28	Bags

Sl no	Particular of Items	Quantity or No's	Rate/Cum	Amount
1	Materilas			
	Cement	28	330	9240
	Sand	4.8	1300	6256.25
	40mm Gauge	9.6	700	6737.5
2	Labours			
	Head Mason	0.25	466	116.5
	Mason	1	456	456
	Mazdoor	8	446	3568
	Coolie	4	446	1784
	Bhisti	2	446	892
	Sundries	-	200	200
Total =				29250.25
Add 1% of water charges =				292.5025
Total =				29542.7525
Add 10% of Profit and loss =				2954.27525
Grand total =				32497.02775