

RATE ANALYSIS – "Plastering in Superstructure"

1. 12MM Brick Cement plastering 1:6 New brick work. Take 100 Sq.M

Given:-

Take 100 Sq.M		
Thickness of Cement floor =	12	mm
Cement =	1	
Sand =	6	
For 1 Cum, Cement required is =	1440	Kg
1 bag of Cement contained is =	50	Kg
Given that Sq.M =	100	Sq.M

Determination of Volume of mortar		
Volume of Mortar =	1.2	Cu.M
Add 10% for unevenes cement base =	1.32	Cu.M
Add 1/3 rd of extra for Dry volume =	1.76	Cu.M
Quantity of Cement =	0.25	Cu.M
No of Cement bags required =	7.24	Nos
No of Cement bags required =	8	Nos
Quantity of Sand =	1.51	Cu.M

Sl no	Particular of Items	Quantity or No's	Rate/Cum	Amount
1	Materials			
	Cement	8	330	2640
	Sand	1.51	1300	1961.1
	Scafflodging	-	200	200
2	Labours			
	Head Mason	1	466	466
	Mason	4	456	1824
	Mazdoor	8	446	3568
	Contengnecies	-	200	200
Total =				10859.14
Add 1% of Water Charges =				108.59
Total =				10967.73
Add 10% of Profit or Loss =				1096.77
Grand Total				12064.51