

Bill of Quantities (BOQ) – "RCC Work in Superstructure"

Calculate the rate analysis for RCC work with CC 1:2:4 including reinforcement. Take 10 Cu.m of Concrete.

Given data :

1 Cum of cement bags contains	1440	Kg
Consider steel at 1% for superstructure =	7.85	Quintal
Cement =	1	Cum
Sand =	2	Cum
Aggregate =	4	Cum
Total =	7	Cum
Take 10 Cum.		
Dry weight:=	Wet weight + 54% of wet-	Cum.
Wet weight =	10	Cum
Dry weight =	15.4	Cum
		Cum
Quantity of cement =	2.2	Cum
Quantity of Sand =	4.4	Cum
Quantity of Aggregate =	8.8	Cum
Number of cement bags in Cum =	0.0347	Cum
Total number of cement bags =	63.36	Bags
Total number of cement bags =	64	Bags

Sl no	Particular of Items	Quantity or	Rate/Cum	Amount
1	Materials			
	Cement	64	330	21120
	Sand	4.40	1300	5720.0
	Aggregate	8.80	700	6160.0
	Steel	7.85	8000	62800.0
	Binding wire	1.50	60	90.0
	Scaffolding	-	200	200
2	Labours			
	Head Mason	1	466	466
	Mason	6	456	2736
	Mazdoor	8	446	3568
	Blacksmith	12	446	5352
	Mazdoor	10	446	4460
	Carpenter	10	446	4460
	Mazdoor	8	446	3568
	Timber planks and ballies	-	500	500
	Contengnecies	-	200	200
Total =				121400.00
Add 1% of Water Charges =				1214.00
Total =				122614.00
Add 10% of Profit or Loss =				12261.40
Grand Total				134875.40